




Received  
Planning Division  
04/17/2019

# CEDAR GROVE



### VICINITY MAP

NTS



## SITE PLAN

SCALE: 1"=50'

## BENCHMARK

VERTICAL DATUM: ELEVATIONS ARE BASED ON USGS BENCHMARK  
"K-206" WITH A PUBLISHED ELEVATION OF 253.26' AND REFERENCED TO  
NGVD '29 DATUM.

### TAX LOT INFORMATION

SECTION 33, TOWNSHIP 1 NORTH, RANGE 1 WEST, OF THE WILLAMETTE  
MERIDIAN, IN THE COUNTY OF WASHINGTON.

## ABBREVIATIONS

AC	ASPHALTIC CONCRETE	IRR	IRRIGATION
AD	AREA DRAIN	LT	LEFT
ASSY	ASSEMBLY	L/S	LANDSCAPE
BO	BLOWOFF	MAX	MAXIMUM
BOW	BACK OF WALK	ME	MATCH EXISTING
BV	BUTTERFLY VALVE	MH	MANHOLE
CB	CATCH BASIN	MIN	MINIMUM
C	CENTERLINE	NTS	NOT TO SCALE
CJ	CONSTRUCTION JOINT	NO	NUMBER
CONC	CONCRETE	OH	OVERHEAD
CONC	CONSTRUCT	OWH	OVERHEAD WIRE
COTG	CLEAN OUT TO GRADE	PC	POINT OF CURVATURE
CP	CONTROL POINT	PIV	POST INDICATOR VALVE
CWS	CLEAN WATER SERVICES	PNT	POINT
DD	DOUBLE CHECK	PRC	POINT OF REVERSE CURVATURE
DDC	DOUBLE DETECTOR CHECK	PT	POINT OF TANGENCY
DI	DUCTILE IRON	PVMT	PAVEMENT
D/W	DRIVEWAY	RD	ROOF DRAIN
DWG	DRAWING	RT	RIGHT
EJ	EXPANSION JOINT	ROW	RIGHT-OF-WAY
ELEV	ELEVATION	S=	SLOPE EQUALS
EP	EDGE OF PAVEMENT	SD	STORM DRAIN
ER	END OF RETURN	SHT	SHEET
EXIST	EXISTING	SS	SANITARY SEWER
E	EXISTING	ST	STREET
FDC	FIRE DEPT. CONNECTION	STD	STANDARD
FDCI	FIRE DEPT. CONNECTION LINE	S/W	SIDEWALK
FF	FINISHED FLOOR ELEV.	TOP OF	TOP OF CURB
FG	FINISHED GRADE	TEL	TELEPHONE
FH	FIRE HYDRANT	TEMP	TEMPORARY
FL	FLOW LINE	TP	TOP OF PAVEMENT
FP	FIRE PROTECTION	TYP	TYPICAL
FWL	FIRE WATER LINE	VG	VALLEY GUTTER
G	GAS	W	WATER
G=	GUTTER EQUALS	W/	WITH
GB	GRADE BREAK	WV	WATER VALVE
GV	GATE VALVE	WSE	WATER SURFACE ELEVATION
IE	INVERT ELEVATION		

## CONTACTS

**OWNER:**  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
6380 SW CAPITOL HWY  
PORTLAND, OR 97239  
PHONE: 503.293.4038  
CONTACT: JILIAN SAURAGE FELTON

ARCHITECT  
CARLETON HART ARCHITECTURE P.C.  
830 SW 10TH AVE, #200  
PORTLAND, OR 97205  
PHONE: 503.206.3187  
CONTACT: MELISSA SOOTS

SURVEYOR  
AKS ENGINEERING & FORESTRY, LLC  
12965 SW HERMAN RD, STE 100  
PORTLAND, OR 97062  
PHONE: 503.563.6151  
CONTACT: NICK WHITE

CIVIL ENGINEER  
HUMBER DESIGN GROUP, INC.  
117 SE TAYLOR ST, STE 001  
PORTLAND, OR 97214  
PHONE: (503) 946-6632  
CONTACT: WILLIAM BRANNAN, PE

GEOTECHNICAL ENGINEER  
ALDER GEOTECHNICAL SERVICES  
3910 NE 10TH AVE  
PORTLAND, OR 97212  
PHONE: 503.282.7482  
CONTACT: JOHN CUNNINGHAM










































LANDSCAPE ARCHITECT  
MARIANNE ZARKIN  
LANDSCAPE ARCHITECTS  
1326 NE 63RD AVE  
PORTLAND, OR 97213  
PHONE: 503.802.0031  
CONTACT: MARIANNE ZARKIN

CONTRACTOR  
LMC CONSTRUCTION CCB 161282  
19200 SW TETON AVE  
TUALATIN, OR 97062  
PHONE: 503.646.6823  
CONTACT: CHRIS DUFFIN

IMPERVIOUS AREA

	WITHIN PRIVATE PROPERTY (SF)
PROPOSED NEW BUILDING	9,357 SF
PROPOSED NEW IMPERVIOUS AREAS OTHER THAN BUILDINGS	18,521 SF
TOTAL IMPERVIOUS AREA	27,878 SF

## LEGEND

<u>EXISTING</u>	<u>PROPOSED</u>	<u>DESCRIPTION</u>
		MANHOLE
		CATCH BASIN
		CLEAN OUT
		FIRE HYDRANT
		WATER METER
		WATER VALVE
		THRUST BLOCK
		LIGHT
		UTILITY POLE
		SIGN
		TREE
		PROPERTY LINE/LOT LINE
		CENTERLINE
		EASEMENT LINE
		CONTOUR
		CURB
		STORM DRAIN
		WATER
		SANITARY SEWER
		UNDERGROUND TELEPHONE
		OVERHEAD UTILITIES
		GAS
		UNDERGROUND POWER
		SILT FENCE
		RETAINING WALL

## SHEET INDEX

C0.00	CIVIL NOTES
C0.01	CIVIL NOTES
C1.00	EXISTING CONDITIONS AND DEMO PLAN
C2.00	OVERALL LAYOUT AND PAVING PLAN
C2.01	LAYOUT AND PAVING PLAN - SOUTH
C2.02	LAYOUT AND PAVING PLAN - NORTH
C3.00	OVERALL GRADING PLAN
C3.01	GRADING PLAN - SOUTH
C3.02	GRADING PLAN - NORTH
C4.00	OVERALL UTILITY PLAN
C4.01	UTILITY PLAN - SOUTH
C4.02	UTILITY PLAN - NORTH
C5.00	CIVIL DETAILS
C5.01	CIVIL DETAILS
C5.02	CIVIL DETAILS
C5.03	CIVIL DETAILS

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT - CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION



**CARLETON HART ARCHITECTURE P.C.**  
830 sw 10th avenue #200 portlandoregon97205  
503 243 2252 | [www.carletonhart.com](http://www.carletonhart.com)



**Humber  
Design  
Group, Inc.**  
Portland, OR • 503.946.6690 • [hdgpdx.com](http://hdgpdx.com)

**CEDAR GROVE**  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON

COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING

## LAND USE REVIEW

COVER SHEET

PROJECT NO.  
15055

04.17.2019

REVISIONS: 

#
---

C0.00



GENERAL NOTES

- ALL CONSTRUCTION, MATERIALS, AND WORKMANSHIP SHALL CONFORM TO THE LATEST STANDARDS AND PRACTICES OF THE CITY OF BEAVERTON, THE OREGON STRUCTURAL SPECIALTY CODE (BUILDING CODE), OREGON PLUMBING SPECIALTY CODE (PLUMBING CODE), AND THE OREGON FIRE CODE (FIRE CODE), LATEST EDITIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING AND SCHEDULING ALL WORK WITH THE OWNER.
- ALL PERMITS AND LICENSES NECESSARY FOR THE EXECUTION AND COMPLETION OF THE WORK SHALL BE SECURED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION.
- ALL EXCAVATORS MUST COMPLY WITH THE RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER, INCLUDING NOTIFICATION OF ALL OWNERS OF UNDERGROUND UTILITIES AT LEAST 48 BUSINESS DAY HOURS, BUT NOT MORE THAN 10 BUSINESS DAYS, BEFORE COMMENCING AN EXCAVATION. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090 AND ORS 757.541 TO 757.57. THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987 AND THE LOCAL "CALL 48 HOURS BEFORE YOU DIG NUMBER" IS 503-246-6699.
- THE LOCATION OF EXISTING UNDERGROUND UTILITIES SHOWN ON THE PLANS IS FOR INFORMATION ONLY AND IS NOT GUARANTEED TO BE ACCURATE. CONTRACTOR SHALL VERIFY ELEVATIONS OF ALL UNDERGROUND UTILITIES PRIOR TO COMMENCING WITH CONSTRUCTION AND SHALL BRING ANY DISCREPANCIES TO THE ATTENTION OF HUMBER DESIGN GROUP. POTHOLE ALL CROSSINGS AS NECESSARY BEFORE CONSTRUCTION TO PREVENT GRADE AND ALIGNMENT CONFLICTS.
- THE ENGINEER OR OWNER IS NOT RESPONSIBLE FOR THE SAFETY OF THE CONTRACTOR OR HIS CREW. ALL O.S.H.A. REGULATIONS SHALL BE STRICTLY ADHERED TO IN THE PERFORMANCE OF THE WORK.
- TEMPORARY AND PERMANENT EROSION CONTROL MEASURES SHALL BE USED AS NEEDED. THE CONTRACTOR SHALL ADHERE TO THE CITY OF BEAVERTON EROSION CONTROL STANDARDS AS NECESSARY FOR EROSION CONTROL MEASURES.
- THE CONTRACTOR IS RESPONSIBLE TO MAINTAIN ALL ROADWAYS CLEAN AND FREE OF CONSTRUCTION MATERIALS AND DEBRIS.
- CONTRACTOR TO ADJUST ALL EXISTING OR NEW FLEXIBLE UTILITIES (WATER, GAS, TV, TELEPHONE, ELEC., ETC.) TO CLEAR ANY EXISTING OR NEW GRAVITY DRAIN UTILITIES (STORM DRAIN, SANITARY SEWER, ETC.) IF CONFLICT OCCURS.
- HUMBER DESIGN GROUP, INC. ASSUMES NO RESPONSIBILITY FOR ANY DISCREPANCIES ENCOUNTERED BETWEEN THE CURRENT FIELD CONDITIONS AND THE INFORMATION SHOWN ON THE SURVEY MAP. THE CONTRACTOR IS RESPONSIBLE FOR REPORTING ANY DISCREPANCIES TO THE OWNER'S REPRESENTATIVE.

GRADING NOTES

- ALL SURFACES SHALL MEET EXISTING GRADES SMOOTHLY AND EVENLY AND MAINTAIN CONSTANT SLOPES UNLESS OTHERWISE NOTED ON PLANS.
  - PEDESTRIAN WALKWAYS 2.0% MAX. CROSS SLOPE.
  - ADA STALLS 2.0% MAX. SLOPE ANY DIRECTION.
  - LANDSCAPE 2.0% MIN. TO DRAIN.
  - ALL OTHER HARDSCAPES 1.0% MIN. TO DRAIN.
- CONTRACTOR RESPONSIBLE FOR MAINTAINING EXISTING SITE AND DRAINAGE PATTERNS AND PROTECTION OF EXISTING ENGINEERED DRAINAGE FACILITIES.
- CONTRACTOR SHALL EXERCISE CARE IN ALL OPERATIONS TO PROTECT EXISTING UNDERGROUND UTILITIES. ANY DAMAGE RESULTING FROM THIS WORK MUST BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THE APPROVAL OF THE OWNER'S REPRESENTATIVE.
- CONTRACTOR SHALL REPLACE AND RESTORE AREAS NOT SCHEDULED FOR CONSTRUCTION TO THEIR ORIGINAL CONDITION AND TO THE APPROVAL OF THE OWNER'S REPRESENTATIVE.
- CONTRACTOR SHALL EXEROISE EXTREME CAUTION WHEN WORKING IN AREAS ADJACENT TO EXISTING TREES IN ORDER TO MINIMIZE DISTURBANCES TO TREE ROOTS. CONTRACTOR SHALL INSTALL TREE PROTECTION FENCING AS INDICATED ON PLANS OR AT DRIP-LINE OF EXISTING TREES. NO PARKING VEHICLES UNDER TREES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION AND DISPOSAL OF EXISTING AC, CURBS, SIDEWALKS AND OTHER SITE ELEMENTS WITHIN THE PROJECT AREA. DISPOSE OF DEMOLISHED ITEMS OFF-SITE IN A LEGAL MANNER.
- ACTUAL LINES AND GRADES OF EXCAVATION SHALL BE STAKED BY QUALIFIED SURVEYOR, BASED ON DIMENSIONS AND BEARINGS AS SHOWN ON THE PLANS CONTRACTOR SHALL RETAIN A SURVEYOR LICENSED IN OREGON.
- ADJUST ALL INCIDENTAL STRUCTURES, MANHOLE LIDS, VALVE BOXES, ETC. TO FINISH GRADE.

PAVING NOTES

- PAVING WILL NOT BE ALLOWED DURING WET OR COLD WEATHER, PER ODOT SPECIFICATIONS.
- ALL CONSTRUCTION WITHIN THE CITY OF BEAVERTON RIGHT-OF-WAY SHALL HAVE AN APPROVED TRAFFIC CONTROL PLAN.
- ALL CONSTRUCTION WITHIN THE CITY RIGHT-OF-WAY SHALL BE PERMITTED UNDER THE BUILDING PERMIT AS SHOWN ON PLANS PER CITY OF BEAVERTON STANDARD SPECIFICATIONS AND STANDARD DRAWINGS.

STORMWATER FACILITY NOTES

- IMPORTED GROWING MEDIUM SHALL MEET REQUIREMENTS LISTED IN CWS DESIGN & CONSTRUCTION STANDARDS APPENDIX A.
- CONTRACTOR SHALL NOT INSTALL IMPORTED GROWING MEDIUM UNTIL PLANTING IS READY TO BE INSTALLED.
- ONCE GROWING MEDIUM IS INSTALLED IT SHALL BE PROTECTED FROM EROSION AND PLANTING SHALL BE INSTALLED AS SOON AS POSSIBLE.
- ROCK MULCH SHALL BE INSTALLED AT BOTTOM OF FACILITY TO PROTECT SOIL FROM EROSION.
- ANY OUTFALL, PIPE OR CURB OPENING SHALL HAVE PROTECTION INSTALLED PRIOR TO RECEIVING RUNOFF.
- ANY PENETRATIONS THROUGH THE IMPERMEABLE LINER SHALL BE WATER TIGHT.

MATERIAL NOTES

- MATERIALS SHALL BE NEW. THE USE OF MANUFACTURER'S NAMES, MODELS, AND NUMBERS IS INTENDED TO ESTABLISH STYLE, QUALITY, APPEARANCE, AND USEFULNESS. PROPOSED SUBSTITUTIONS WILL REQUIRE WRITTEN APPROVAL FROM CITY ENGINEER PRIOR TO INSTALLATION.
- ALL ON-SITE WATER, STORM AND SANITARY SEWER PIPE MATERIALS, FITTINGS SHALL CONFORM TO THE OREGON STATE PLUMBING SPECIALTY CODE, LATEST EDITION.
- ON-SITE WATER MAINS SHALL BE DUCTILE IRON PIPE, CLASS 52, CONFORMING TO AWWA C151 OR APPROVED SPEC SUBSTITUTIONS. WATER MAIN BETWEEN THE METER VAULT AND BACKFLOW VAULT SHALL BE COPPER TUBING CONFORMING TO ASTM B88, SILVER SOLDER, OR APPROVED SUBSTITUTIONS.
- ON-SITE STORM SEWER PIPE SHALL BE PVC PIPE CONFORMING TO ASTM D3034 SDR 35, OR HDPE PIPE (ADS 'N-12' OR APPROVED EQUAL) CONFORMING TO AASHTO M252 W/WATERTIGHT JOINTS, OR APPROVED SUBSTITUTIONS.
- ON-SITE STORM SEWER PIPE WITH LESS THAN 2' OF COVER SHALL BE HDPE PIPE.
- ON-SITE AREA DRAINS SHALL BE MANUFACTURED BY LYNCH CO., INC. OR APPROVED EQUAL.
- ON-SITE SANITARY SEWER PIPE SHALL BE PVC PIPE CONFORMING TO ASTM D3034, SDR 35, OR APPROVED SUBSTITUTIONS.

UTILITY NOTES

- ALL WATER AND SANITARY SEWER FACILITIES AND THE INSTALLATION THEREOF, SHALL FOLLOW THE CURRENT OREGON STATE PLUMBING SPECIALTY CODE AND THE CURRENT EDITION OF APWA WITH CITY OF BEAVERTON INSPECTION DURING CONSTRUCTION.
- ALL TRENCH BACKFILL SHALL BE AS SHOWN ON THE PIPE BEDDING AND BACKFILL DETAIL. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER IS NOT PERMITTED.
- CONNECTIONS TO EXISTING UTILITIES SHALL CONFORM WITH THE CITY OF BEAVERTON ENGINEERING DESIGN MANUAL AND STANDARD DRAWINGS.
- ALL WATER AND FIRE PROTECTION PIPE SHALL HAVE MINIMUM 36-INCH COVER TO FINISHED GRADE.
- ALL WATER LINES SHALL BE THOROUGHLY FLUSHED, CHLORINATED AND TESTED IN ACCORDANCE WITH THE OREGON STATE HEALTH DEPARTMENT PRIOR TO ANY METER HOOK-UP SERVICE.
- BEGIN LAYING STORM AND SANITARY SEWER PIPE AT THE LOW POINT OF THE SYSTEM TRUE TO GRADE AND ALIGNMENT INDICATED WITH UNBROKEN CONTINUITY OF INVERT. ESTABLISH LINE AND GRADE FOR THE STORM AND SANITARY SEWER PIPE BY THE USE OF A LASER.
- CONTRACTOR SHALL PREVENT SEDIMENTS FROM ENTERING THE STORM DRAINAGE SYSTEM.
- CONTRACTOR TO MAINTAIN A MINIMUM 10' HORIZONTAL AND 18" VERTICAL SEPARATION BETWEEN ALL EXISTING AND PROPOSED WATER AND SEWER LINES.
- FOR CROSSINGS OF WATER LINES AND SANITARY SEWER LINES, THE OREGON STATE HEALTH DEPARTMENT CRITERIA SHALL APPLY.
- DOMESTIC WATER SERVICE BACKFLOW ASSEMBLY SHALL BE INSTALLED PRIOR TO ANY BRANCHES IN THE DOMESTIC PLUMBING SYSTEM.
- BACKFLOW ASSEMBLY(IES) TO BE INSTALLED AT THE POINT WHERE THE WATER SERVICE ENTERS THE PROPERTY. IF APPROVED TO BE INSTALLED INSIDE OF BUILDING, ASSEMBLY(S) MUST BE INSTALLED AT THE POINT WHERE SERVICE ENTERS, BETWEEN ONE AND FIVE FEET ABOVE THE FLOOR. ALTERNATE LOCATIONS MUST BE APPROVED BY WATER QUALITY INSPECTORS, PUBLIC WORKS DEPARTMENT (503-526-2220).
- IF THE REDUCE PRESSURE (RP) BACKFLOW ASSEMBLY IS REQUIRED IT MUST BE INSTALLED AT LEAST 12" ABOVE FINISHED GRADE. RP DEVICE IS REQUIRED IF PROJECT IS HARVESTING RAINWATER.
- CITY OF BEAVERTON SANITATION PERMIT REQUIRED TO DECOMMISSION EXISTING RESIDENTIAL CESSPOOLS OR DRYWELLS DISCOVERED DURING CONSTRUCTION.
- EXISTING STORM OR SANITARY LATERALS TO BE UTILIZED FOR NEW SYSTEM MUST BE VIDEO INSPECTED WITH CITY INSPECTOR PRESENT PRIOR TO CONNECTION.
- ALL WATER WORK IN THE PUBLIC RIGHT OF WAY IS BY THE CITY OF BEAVERTON PUBLIC WORKS DEPARTMENT. CONTRACTOR SHALL COORDINATE WITH PUBLIC WORKS AT 503-526-2220.
- ALL NEW DRYWELLS MUST BE ACCESSIBLE PER OREGON DEPARTMENT OF ENVIRONMENTAL SERVICES QUALITY REQUIREMENT.
- PGE OR PACIFIC POWER SHALL OBTAIN PERMIT FROM CITY OF BEAVERTON TO INSTALL CONDUIT IN PUBLIC RIGHT OF WAY.
- CONTRACTOR SHALL VACUUM OUT ALL TRAPPED INLETS, MANHOLES, AND DRYWELLS AT END OF PROJECT.

DUST CONTROL NOTES:

- DUST SHALL BE MINIMIZED TO THE EXTENT PRACTICABLE, UTILIZING ALL MEASURES NECESSARY, INCLUDING, BUT NOT LIMITED TO:
  - SPRINKLER HAUL AND ACCESS ROADS AND OTHER EXPOSED DUST PRODUCING AREAS.
  - APPLYING AGENCY-APPROVED DUST PALLIATIVES ON ACCESS AND HAUL ROADS.
  - ESTABLISHING TEMPORARY VEGETATIVE COVER.
  - PLACING WOOD CHIPS OR OTHER EFFECTIVE MULCHES ON VEHICLE AND PEDESTRIAN USE AREAS.
  - MAINTAINING THE PROPER MOISTURE CONDITION ON ALL FILL SURFACES.
  - PREWETTING CUT AND BORROW AREA SURFACES.
  - USE OF HAUL EQUIPMENT.
- CONTRACTOR SHALL FURNISH AND INSTALL EQUIPMENT TO HAUL AND PLACE WATER. AN ADEQUATE SUPPLY OF WATER SHALL BE MAINTAINED AT ALL TIMES.

EROSION CONTROL NOTES

- APPROVAL OF THIS EROSION, SEDIMENT AND POLLUTION CONTROL PLAN (ESPCP) DOES NOT CONSTITUTE AN APPROVAL OF PERMANENT ROAD OR DRAINAGE DESIGN (E.G., SIZE AND LOCATION OF ROADS, PIPES, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITIES, ETC.)
- IT IS THE INTENT OF THESE PLANS AND SPECIFICATIONS TO ENSURE THAT SEDIMENT LADEN WATER DOES NOT LEAVE THE WORK SITE. THE CONTRACTOR SHALL USE ALL AVAILABLE MEANS TO ACHIEVE THIS RESULT.
- THE IMPLEMENTATION OF THESE ESPCP AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESPCP FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- THE BOUNDARY OF THE CLEARING LIMITS SHOWN ON THIS PLANS SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- THE ESPCP FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO INSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DOES NOT ENTER THE DRAINAGE SYSTEM, ROADWAYS OR VIOLATE APPLICABLE WATER STANDARDS.
- THE ESPCP FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESPCP FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- THE ESPCP FACILITIES SHALL BE INSPECTED DAILY BY CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- THE ESPCP FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITH IN THE 24 HOURS FOLLOWING A STORM EVENT.
- ALL STORM INLETS SHALL BE PROTECTED TO PREVENT SEDIMENT FROM LEAVING THE PROJECT SITE. CLEANING OF CATCH BASINS SHALL OCCUR WHEN SEDIMENT CONSUMES ONE-THIRD OF THE DEVICE STORAGE AREA. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT LADEN WATER INTO THE DOWNSTREAM SYSTEM.
- ALL AREAS DISTURBED BY CONSTRUCTION OF THIS PROJECT, NOT RECEIVING A HARD, DURABLE SURFACE SHALL BE GRASSED AND/OR LANDSCAPED AT EARLIEST PRACTICABLE TIME.
- IN GENERAL, CONSTRUCTION SHALL PROGRESS FROM DOWNSTREAM TO UPSTREAM. THE CONTRACTOR SHALL CONSTRUCT ESC FACILITIES IN CONJUNCTION WITH ALL CLEARING, GRADING AND OTHER LAND ALTERATION ACTIVITIES.
- STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- TEMPORARY EROSION CONTROL MEASURES SHALL REMAIN FUNCTIONAL AND IN PLACE UNTIL THEIR REMOVAL IS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL COMPLETELY RESTORE ALL AREAS DISTURBED BY REMOVAL OF TEMPORARY EROSION CONTROL MEASURES. REMOVED MATERIALS SHALL BECOME PROPERTY OF THE CONTRACTOR TO BE DISPOSED OF IN ACCORDANCE WITH APPLICABLE LAWS AND JURISDICTIONS.
- CONTRACTOR WILL PROVIDE TRUCKS THAT ARE WELL SEALED FOR TRANSPORTATION OF SATURATED SOILS/MATERIAL FROM THE SITE. A TRUCK MUST NOT LEAK LIQUIDS AT ANY RATE GREATER THAN 1 GAL./HR.
- EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH CWS DESIGN & CONSTRUCTION STANDARDS MANUAL.
- SUPPLEMENTARY WET WEATHER MEASURES SHALL BE IN PLACE AND FUNCTIONING BY OCTOBER 1 AND REMAIN OPERATIONAL UNTIL APRIL 30.
- SUPPLEMENTARY WET WEATHER MEASURES ARE IN ADDITION TO BASE MEASURES.
- WHEN CONCRETE TRUCKS ARE USED, A SHALLOW PIT SHALL BE DUG FOR RESIDUAL CONCRETE, AGGREGATE AND WATER. TRUCKS THAT RECYCLE THIS RESIDUAL BACK INTO THE TRUCK MAY BE USED IN LIEU OF THE PIT.
- IF FERTILIZERS ARE USED TO ESTABLISH VEGETATION, THE APPLICATION RATES SHALL FOLLOW THE MANUFACTURER'S GUIDELINES AND THE APPLICATION SHALL BE DONE IN SUCH A WAY TO MINIMIZE NUTRIENT-LADEN RUNOFF TO RECEIVING WATERS.
- STOCKPILES SHALL BE LOCATED AWAY FROM THE CONSTRUCTION ACTIVITY AND SHALL BE STABILIZED OR COVERED AT THE END OF EACH WORKDAY.
- SIGNIFICANT AMOUNTS OF SEDIMENT THAT LEAVE THE SITE SHALL BE CLEANED UP WITHIN 24 HOURS AND PLACED BACK ON THE SITE OR PROPERLY DISPOSED.
- ALL EROSION AND SEDIMENT CONTROLS NOT IN THE DIRECT PATH OF WORK SHALL BE INSTALLED BEFORE ANY LAND DISTURBANCE.

SEDIMENT FENCE NOTES

- THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPICED TOGETHER ONLY AT SUPPORT POST, WITH A 6-INCH MINIMUM OVERLAP, AND BOTH END SECURELY FASTENED TO THE POST, OR OVERLAP 2"x2" POSTS AND ATTACHED AS SHOWN IN SEDIMENT FENCE DETAIL INCLUDED IN THESE PLANS.
- THE FILTER FABRIC FENCE SHALL BE INSTALLED TO FOLLOW THE CONTOURS WHERE FEASIBLE. THE FENCE POSTS SHALL BE SPACED A MAXIMUM OF 6- FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24-INCHES.
- A TRENCH SHALL BE CUT ALONG SLOPE CONTOURS AND AROUND STOCKPILES FOR SILT FENCE INSTALLATION. THE FILTER FABRIC FENCE SHALL HAVE A MINIMUM VERTICAL BURIAL OF 6-INCHES. ALL EXCAVATED MATERIAL FROM THE FILTER FABRIC FENCE INSTALLATION SHALL BE FIRMLY REDEPOSITED ALONG THE ENTIRE TRENCHED AREA ON THE UPHILL SIDE OF AND AGAINST THE FENCE.
- STANDARD OR HEAVY DUTY FILTER FABRIC SHALL HAVE MANUFACTURED STITCHED LOOPS TO FIT 2"x2" INSTALLATION POST. STAPLED FENCE PRODUCTS ARE NOT ALLOWED. STITCHED LOOPS SHALL BE INSTALLED ON THE UPHILL SIDE OF THE SLOPED AREA, WITH POST SPACED A MAXIMUM OF 6 FEET APART.
- FILTER FABRIC FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UP SLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED.
- SILT FENCES SHALL BE INSPECTED BY CONTRACTOR IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS, RELOCATIONS, OR ADDITIONS SHALL BE MADE IMMEDIATELY.
- AT NO TIME SHALL MORE THAN 1-FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE UP SLOPE OF A SILT FENCE. SEDIMENT SHALL BE REMOVED OR RE-GRADED ONTO SLOPES AND THE SILT FENCE REPAIRED AND REESTABLISHED.



CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW

CIVIL NOTES

PROJECT NO.  
15055

04.17.2019

REVISIONS: #

C0.01

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT - CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION





H

Portland, OR • 503.946.6690 • [hdqpdx.com](http://hdqpdx.com)


## LAND USE REVIEW

C1.00

1 inch = 20 ft


SCALE: 1"=20'





OVERALL LAYOUT AND PAVING PLAN  
SCALE: 1"=20'

SHEET LEGEND		
	CONCRETE SIDEWALK	<div><div>1</div><div>C5.01</div></div> <div><div>4</div><div>C5.02</div></div>
	ASPHALT PAVEMENT	<div><div>4</div><div>C5.01</div></div>
	RESIDENTIAL DRIVEWAY APPROACH	<div><div>2</div><div>C5.02</div></div>
	CAST-IN-PLACE WALL	
	STANDARD CONCRETE CURB	<div><div>2</div><div>C5.01</div></div>
	SAWCUT	
	LANDSCAPING	SEE LANDSCAPE PLANS
	STORMWATER PLANTER	<div><div>11</div><div>C5.00</div></div>
	NO PARKING FIRE LANE SIGNAGE AND STRIPING (RED)	



NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT: CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION

REVISIONS: /#

PROJECT NO.  
15055

04.17.2019

OVERALL LAYOUT & PAVING PLAN

CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING

LAND USE REVIEW

Humber  
Design  
Group, Inc.


Portland, OR • 503.946.6690 • hdbgdx.com





CARLETON HART ARCHITECTURE P.C.  
503.243.2252  
www.carletonhart.com

REGISTERED PROFESSIONAL  
ENGINEER  
64500  
OREGON  
WILLIAM G. BRANNAN  
JUNE 1, 2017  
EXPIRES 12-31-19





SHEET LEGEND		
	CONCRETE SIDEWALK	$\frac{1}{C5.01}$ $\frac{4}{C5.02}$
	ASPHALT PAVEMENT	$\frac{4}{C5.01}$
	RESIDENTIAL DRIVEWAY APPROACH	$\frac{2}{C5.02}$
	CAST-IN-PLACE WALL	
	STORM WATER RETAINING WALL	SEE STRUCTURAL PLANS
	STANDARD CONCRETE CURB	$\frac{2}{C5.01}$
	SAWCUT	
	LANDSCAPING	SEE LANDSCAPE PLANS
	STORMWATER PLANTER	$\frac{10}{C5.00}$
	NO PARKING FIRE LANE SIGNAGE AND STRIPING (RED)	



CARLETON HART ARCHITECTURE P.C.  
503.243.2252  
www.carletonhart.com



CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW

LAYOUT & PAVING PLAN - SOUTH

PROJECT NO.  
15055


04.17.2019

REVISIONS: /#


NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT: CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION

C2.01






SHEET LEGEND		
	CONCRETE SIDEWALK	<div><div>1</div><div>C5.01</div></div> <div><div>4</div><div>C5.02</div></div>
	ASPHALT PAVEMENT	<div><div>4</div><div>C5.01</div></div>
	RESIDENTIAL DRIVEWAY APPROACH	<div><div>2</div><div>C5.02</div></div>
	CAST-IN-PLACE WALL	
	STANDARD CONCRETE CURB	<div><div>2</div><div>C5.01</div></div>
	SAWCUT	
	LANDSCAPING	SEE LANDSCAPE PLANS
	STORMWATER PLANTER	<div><div>10</div><div>C5.00</div></div>
	NO PARKING FIRE LANE SIGNAGE AND STRIPING (RED)	



LAYOUT AND PAVING PLAN - NORTH  
SCALE: 1"=10'



CARLETON HART ARCHITECTURE P.C.  
503.243.2252  
www.carletonhart.com



CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW

LAYOUT & PAVING PLAN - NORTH


PROJECT NO.  
15055

04.17.2019

REVISIONS: /#

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT - CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION






OVERALL GRADING PLAN  
SCALE: 1"=20'

SHEET LEGEND	
	EXISTING CONTOUR
	PROPOSED CONTOUR – MAJOR
	PROPOSED CONTOUR – MINOR
	SAWCUT
	GRADEBREAK LINE
	SWALE
TS	TOP OF STAIRS
BS	BOTTOM OF STAIRS
G	GRADE AT GUTTER
TC XXX.XX	GRADE AT TOP OF CURB
TP XXX.XX	GRADE AT TOP OF PAVEMENT
FF XXX.XX	FINISHED FLOOR ELEVATION
FG XXX.XX	FINISHED GRADE
TW XXX.XX	TOP OF WALL ELEVATION
BW XXX.XX	BOTTOM OF WALL ELEVATION
(E)	EXISTING
	SLOPE ARROW
	INLET PROTECTION
	SEDIMENT FENCE


- | SHEET NOTES |   |
|-------------|---|
| 1.          | ALL LANDSCAPED AREAS WITHIN 5–FEET OF THE BUILDING PERIMETER WILL SLOPE AWAY FROM THE FOUNDATION – MINIMUM 5%         |
| 2.          | HARDSCAPE AREAS WILL BE SLOPED A MINIMUM OF 1/4" PER FOOT AWAY FROM THE FOUNDATION AND HAVE MAXIMUM CROSS SLOPE OF 2% |
| 3.          | INSTALL INLET PROTECTION ON ALL STORM INLETS 100' FROM SITE.  |











GRADING PLAN - NORTH  
SCALE: 1"=10'

SHEET LEGEND

---

EXISTING CONTOUR

XXX

PROPOSED CONTOUR - MAJOR

XXX

PROPOSED CONTOUR - MINOR

---

SAWCUT

---

GRADEBREAK LINE

---

SWALE

TS

TOP OF STAIRS

BS

BOTTOM OF STAIRS

G

GRADE AT GUTTER

TC XXX.XX

GRADE AT TOP OF CURB

TP XXX.XX

GRADE AT TOP OF PAVEMENT

FF XXX.XX

FINISHED FLOOR ELEVATION

FG XXX.XX

FINISHED GRADE

TW XXX.XX

TOP OF WALL ELEVATION

BW XXX.XX

BOTTOM OF WALL ELEVATION

(E)

EXISTING

2.0%

SLOPE ARROW

INLET PROTECTION

SEDIMENT FENCE

6

C5.02

5

C5.02

SHEET NOTES

1. ALL LANDSCAPED AREAS WITHIN 5- FEET OF THE BUILDING PERIMETER WILL SLOPE AWAY FROM THE FOUNDATION - MINIMUM 5%

2. HARDSCAPE AREAS WILL BE SLOPED A MINIMUM OF 1" PER FOOT AWAY FROM THE FOUNDATION AND HAVE MAXIMUM CROSS SLOPE OF 2%

3. INSTALL INLET PROTECTION ON ALL STORM INLETS 100' FROM SITE.

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT: CARLETON HART ARCHITECTURE P.C. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT IS TO BE REPRODUCED WITHOUT PERMISSION.

REGISTERED PROFESSIONAL  
ENGINEER  
64500  
OREGON  
WILLIAM G. BRANNAN  
JUNE 1, 2017

EXPIRES 12-31-19

CARLETON HART ARCHITECTURE P.C.  
503.243.2252  
www.carletonhart.com


Humber  
Design  
Group, Inc.  
Portland, OR • 503.946.6690 • hdgpx.com

CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW


GRADING PLAN - NORTH  
PROJECT NO.  
15055  
04.17.2019  
REVISIONS: /#

C3.02





OVERALL UTILITY PLAN  
SCALE: 1"=20'



SHEET ABBREVIATIONS

AD	AREA DRAIN
BWV	BACK WATER VALVE (CLEAN CHECK VALVE)
COTG	CLEAN OUT TO GRADE
DCBA	DOUBLE CHECK BACKFLOW ASSEMBLY
DWCTB	DOMESTIC WATER CONNECTION TO BUILDING
EX	EXISTING
FD	FOUNDATION DRAIN
FDC	FIRE DEPARTMENT CONNECTION
FS	FIRE SERVICE (SPRINKLER WATER)
FSCTB	FIRE SERVICE CONNECTION TO BUILDING
FSV	FIRE SERVICE VAULT
OD	OVERFLOW DRAIN
POC	POINT OF CONNECTION
SD	STORM SEWER
SDPOC	STORM SEWER POINT OF CONNECTION
SS	SANITARY SEWER
WM	WATER METER

SHEET LEGEND

SYMBOL	DESCRIPTION
	PROPOSED STORM DRAIN
	FOUNDATION DRAIN
	PROPOSED SANITARY DRAIN
	PROPOSED DOMESTIC WATER
	PROPOSED FIRE WATER
	EXISTING POWER
	EXISTING NATURAL GAS LINE
	EXISTING TELEPHONE
	DOUBLE CHECK BACKFLOW ASSEMBLY (DCBA)
	WATER METER VAULT
	FIRE SERVICE VAULT (FSV)
	FIRE DEPARTMENT CONNECTION (FDC)
	CATCH BASIN
	AREA DRAIN
	STORMWATER PLANTER
	PROPOSED HYDRANT
	TRENCH DRAIN

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT: CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION



CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW

OVERALL UTILITY PLAN


PROJECT NO.  
15055

04.17.2019

REVISIONS: /#

C4.00






### SHEET ABBREVIATIONS

AD	AREA DRAIN
BWV	BACK WATER VALVE (CLEAN CHECK VALVE)
COTG	CLEAN OUT TO GRADE
DCBA	DOUBLE CHECK BACKFLOW ASSEMBLY
DWCTB	DOMESTIC WATER CONNECTION TO BUILDING
EX	EXISTING
FD	FOUNDATION DRAIN
FDC	FIRE DEPARTMENT CONNECTION
FS	FIRE SERVICE (SPRINKLER WATER)
FSCTB	FIRE SERVICE CONNECTION TO BUILDING
FSV	FIRE SERVICE VAULT
OD	OVERFLOW DRAIN
POC	POINT OF CONNECTION
SD	STORM SEWER
SDPOC	STORM SEWER POINT OF CONNECTION
SS	SANITARY SEWER
WM	WATER METER

### SHEET LEGEND

SYMBOL	DESCRIPTION
	PROPOSED STORM DRAIN
	FOUNDATION DRAIN
	PROPOSED SANITARY DRAIN
	PROPOSED DOMESTIC WATER
	PROPOSED FIRE WATER
	EXISTING POWER
	EXISTING NATURAL GAS LINE
	EXISTING TELEPHONE
	DOUBLE CHECK BACKFLOW ASSEMBLY (DCBA)
	WATER METER VAULT
	FIRE SERVICE VAULT (FSV)
	FIRE DEPARTMENT CONNECTION (FDC)
	CATCH BASIN
	AREA DRAIN
	STORMWATER PLANTER
	PROPOSED HYDRANT
	TRENCH DRAIN



CARLETON HART ARCHITECTURE P.C.  
503.243.2252  
www.carletonhart.com



CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW

UTILITY PLAN - SOUTH

PROJECT NO.  
15055

04.17.2019


REVISIONS: /#

C4.01

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT: CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION




MATCHLINE SEE SHEET 4.02



SHEET ABBREVIATIONS	
AD	AREA DRAIN
BWV	BACK WATER VALVE (CLEAN CHECK VALVE)
COTG	CLEAN OUT TO GRADE
DCBA	DOUBLE CHECK BACKFLOW ASSEMBLY
DWCTB	DOMESTIC WATER CONNECTION TO BUILDING
EX	EXISTING
FD	FOUNDATION DRAIN
FDC	FIRE DEPARTMENT CONNECTION
FS	FIRE SERVICE (SPRINKLER WATER)
FSCTB	FIRE SERVICE CONNECTION TO BUILDING
FSV	FIRE SERVICE VAULT
OD	OVERFLOW DRAIN
POC	POINT OF CONNECTION
SD	STORM SEWER
SDPOC	STORM SEWER POINT OF CONNECTION
SS	SANITARY SEWER
WM	WATER METER

SHEET LEGEND	
SYMBOL	DESCRIPTION
	PROPOSED STORM DRAIN
	FOUNDATION DRAIN
	PROPOSED SANITARY DRAIN
	PROPOSED DOMESTIC WATER
	PROPOSED FIRE WATER
	EXISTING POWER
	EXISTING NATURAL GAS LINE
	EXISTING TELEPHONE
	DOUBLE CHECK BACKFLOW ASSEMBLY (DCBA)
	WATER METER VAULT
	FIRE SERVICE VAULT (FSV)
	FIRE DEPARTMENT CONNECTION (FDC)
	CATCH BASIN
	AREA DRAIN
	STORMWATER PLANTER
	PROPOSED HYDRANT
	TRENCH DRAIN



UTILITY PLAN - NORTH  
SCALE: 1"=10'

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11x17  
COPYRIGHT: CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION



CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW

UTILITY PLAN - NORTH


PROJECT NO.  
15055  
04.17.2019

REVISIONS: #












## 8 FIRE HYDRANT

NTS




## 7 3" WATER METER VAULT

NTS




## 5 FIRE SERVICE VAULT

NTS




## 4 ASPHALT PAVEMENT SECTION

NTS




## 3 POST INDICATOR VALVE

NTS





## 2 CONCRETE CURB (PRIVATE)

NTS



## 1 CONCRETE SIDEWALK (PRIVATE)

NTS



**CEDAR GROVE**  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR AFFORDABLE HOUSING  
LAND USE REVIEW

**CIVIL DETAILS**

**PROJECT NO. 15055**


**04.17.2019**

**REVISIONS: #**

**C5.01**

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT: CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION





**WOVEN POLYPROPLENE SACK**

**NOTE:**


1. RECESSED CURB INLET CATCH BASINS MUST BE BLOCKED WHEN USING FILTER FABRIC INLET SACKS. SIZE OF FILTER FABRIC INLET SACKS TO BE DETERMINED BY MANUFACTURER.

**INLET PROTECTION TYPE 5**

DETAIL DRAWING 4-19 REVISED 01-09


**6 FILTER FABRIC INLET PROTECTION**

NTS




**5 SEDIMENT FENCE**

NTS




**4 STANDARD PUBLIC CONCRETE SIDEWALK**

NTS




**2 STANDARD RESIDENTIAL DRIVEWAY**

NTS




**3 RECYCLED RUBBER WHEELSTOP**

NTS



**1 STANDARD MANHOLE**

NTS



**CARLETON HART ARCHITECTURE P.C.**  
503.243.2252  
www.carletonhart.com



**CEDAR GROVE**  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING  
LAND USE REVIEW

CIVIL DETAILS

PROJECT NO.  
15055



04.17.2019

REVISIONS: #

**C5.02**

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT - CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION





CARLETON HART ARCHITECTURE P.C.  
503.243.2252  
www.carletonhart.com



Portland, OR • 503.946.6690 • hdgpdx.com

CEDAR GROVE  
812 & 822 NW MURRAY BLVD.  
BEAVERTON, OREGON  
COMMUNITY PARTNERS FOR  
AFFORDABLE HOUSING

LAND USE REVIEW


CIVIL DETAILS

PROJECT NO.  
15055

04.17.2019

REVISIONS: /#

NOTE: DRAWINGS ARE AT HALF SCALE WHEN PRINTED AT 11X17  
COPYRIGHT: CARLETON HART ARCHITECTURE DO NOT REPRODUCE WITHOUT PERMISSION



1

STORMWATER FACILITY CONSTRUCTION SLOPE

NTS

C5.03